PHILIPS 74ABT2245 transceiver datasheet

http://www.manuallib.com/philips/74abt2245-transceiver-datasheet.html

The 74HC2G86; 74HCT2G86 is a dual 2-input EXCLUSIVE-OR gate. Inputs include clamp diodes that enable the use of current limiting resistors to interface inputs to voltages in excess of VCC.

DATA SHEET

74ABT2245

Octal transceiver with direction pin and 30 Ω series termination resistors (3-State)

Product data
Supersedes data of 1998 Jan 16

2002 Dec 17

Philips
Semiconductors

PHILIPS

PHILIPS

Octal transceiver with direction pin and 30 Ω series termination resistors (3-State)

74ABT2245

FEATURES

- Octal bidirectional bus interface

- 3-State buffers

- Output capability: +12 mA / −32 mA

- Latch-up protection exceeds 500 mA per Jedec Std 17

- ESD protection exceeds 2000 V per MIL STD 833 Method 3015 and 200 V per Machine Model

- Power-up 3-State

- Live insertion/extraction permitted

- Same as 74ABT245-1

- Outputs include series resistance of 30 Ω, making external termination resistors unnecessary

- Inputs are disabled during 3-State mode

DESCRIPTION

The 74ABT2245 high-performance BiCMOS device combines low static and dynamic power dissipation with high speed.

The 74ABT2245 device is an octal transceiver featuring non-inverting 3-State bus compatible outputs in both send and receive directions. The control function implementation minimizes external timing requirements. The device features an Output Enable ($\overline{OE}$) input for easy cascading and a Direction (DIR) input for direction control.

The 74ABT2245 is designed with 30 Ω series resistance in both the HIGH and LOW states of the output. This design reduces line noise in applications such as memory address drivers, clock drivers, and bus receivers/transmitters.

The 74ABT2245 is the same as the 74ABT245-1. The part number has been changed to reflect industry standards.

QUICK REFERENCE DATA

SYMBOL	PARAMETER	CONDITIONS T_{amb} = 25 °C; GND = 0 V	TYPICAL	UNIT
t_{PLH} t_{PHL}	Propagation delay An to Bn or Bn to An	C_L = 50 pF; V_{CC} = 5 V	3.9	ns
C_{IN}	Input capacitance DIR, $\overline{OE}$	V_I = 0 V or V_{CC}	4	pF
$C_{I/O}$	I/O pin capacitance	Outputs disabled; V_O = 0 V or V_{CC}	7	pF
I_{CCZ}	Total supply current	Outputs disabled; V_{CC} = 5.5 V	50	µA

ORDERING INFORMATION

PACKAGES	TEMPERATURE RANGE	PART NUMBER	DWG NUMBER
20-Pin plastic SO	−40 °C to +85 °C	74ABT2245D	SOT163-1
20-Pin Plastic SSOP Type II	−40 °C to +85 °C	74ABT2245DB	SOT339-1
20-Pin Plastic TSSOP Type I	−40 °C to +85 °C	74ABT2245PW	SOT360-1

PIN CONFIGURATION


```
DIR   1        20  V_CC
A0    2        19  OE
A1    3        18  B0
A2    4        17  B1
A3    5        16  B2
A4    6        15  B3
A5    7        14  B4
A6    8        13  B5
A7    9        12  B6
GND  10        11  B7
```
SA00121

PIN DESCRIPTION

PIN NUMBER	SYMBOL	NAME AND FUNCTION
1	DIR	Direction control input
2, 3, 4, 5, 6, 7, 8, 9	A0 – A7	Data inputs/outputs (A side)
18, 17, 16, 15, 14, 13, 12, 11	B0 – B7	Data inputs/outputs (B side)
19	$\overline{OE}$	Output enable input (active-LOW)
10	GND	Ground (0 V)
20	V_{CC}	Positive supply voltage

2002 Dec 17   2

Octal transceiver with direction pin and 30 Ω series termination resistors (3-State)

74ABT2245

LOGIC SYMBOL

SA00122

LOGIC SYMBOL IEEE/IEC

SA00313

FUNCTION TABLE

INPUTS		INPUTS/OUTPUTS	
$\overline{OE}$	DIR	An	Bn
L	L	An = Bn	Inputs
L	H	Inputs	Bn = An
H	X	Z	Z

H = High voltage level
L = Low voltage level
X = Don't care
Z = High impedance "off" state

SCHEMATIC OF EACH OUTPUT

SA00237

ABSOLUTE MAXIMUM RATINGS[1, 2]

SYMBOL	PARAMETER	CONDITIONS	RATING	UNIT
V_{CC}	DC supply voltage		−0.5 to +7.0	V
I_{IK}	DC input diode current	$V_I < 0$ V	−18	mA
V_I	DC input voltage[3]		−1.2 to +7.0	V
I_{OK}	DC output diode current	$V_O < 0$ V	−50	mA
V_{OUT}	DC output voltage[3]	output in Off or HIGH state	−0.5 to +5.5	V
I_{OUT}	DC output current	output in LOW state	128	mA
T_{stg}	Storage temperature range		−65 to 150	°C

NOTES:
1. Stresses beyond those listed may cause permanent damage to the device. These are stress ratings only and functional operation of the device at these or any other conditions beyond those indicated under "recommended operating conditions" is not implied. Exposure to absolute-maximum-rated conditions for extended periods may affect device reliability.
2. The performance capability of a high-performance integrated circuit in conjunction with its thermal environment can create junction temperatures which are detrimental to reliability. The maximum junction temperature of this integrated circuit should not exceed 150 °C.
3. The input and output voltage ratings may be exceeded if the input and output current ratings are observed.

RECOMMENDED OPERATING CONDITIONS

SYMBOL	PARAMETER	LIMITS		UNIT
		Min	Max	
V_{CC}	DC supply voltage	4.5	5.5	V
V_I	Input voltage	0	V_{CC}	V
V_{IH}	HIGH-level input voltage	2.0	–	V
V_{IL}	LOW-level Input voltage	–	0.8	V
I_{OH}	HIGH-level output current	–	−32	mA
I_{OL}	LOW-level output current	–	12	mA
$\Delta t/\Delta v$	Input transition rise or fall rate	0	5	ns/V
T_{amb}	Operating free-air temperature range	−40	+85	°C

Octal transceiver with direction pin and
30 Ω series termination resistors (3-State)

74ABT2245

DC ELECTRICAL CHARACTERISTICS

SYMBOL	PARAMETER		TEST CONDITIONS	LIMITS					UNIT
				T_{amb} = +25 °C			T_{amb} = −40 °C to +85 °C		
				Min	Typ	Max	Min	Max	
V_{IK}	Input clamp voltage		V_{CC} = 4.5 V; I_{IK} = −18 mA	–	−0.9	−1.2	–	−1.2	V
V_{OH}	HIGH-level output voltage		V_{CC} = 4.5 V; I_{OH} = −3 mA; V_I = V_{IL} or V_{IH}	2.5	2.9	–	2.5	–	V
			V_{CC} = 5.0 V; I_{OH} = −3 mA; V_I = V_{IL} or V_{IH}	3.0	3.4	–	3.0	–	V
			V_{CC} = 4.5 V; I_{OH} = −32 mA; V_I = V_{IL} or V_{IH}	2.0	2.4	–	2.0	–	V
V_{OL}	LOW-level output voltage		V_{CC} = 4.5 V; I_{OL} = 5 mA; V_I = V_{IL} or V_{IH}	–	0.32	0.55	–	0.55	V
			V_{CC} = 4.5 V; I_{OL} = 12 mA; V_I = V_{IL} or V_{IH}	–	0.5	0.8	–	0.8	V
I_I	Input leakage current	Control pins	V_{CC} = 5.5 V; V_I = GND or 5.5 V	–	±0.01	±1.0	–	±1.0	µA
		Data pins	V_{CC} = 5.5 V; V_I = GND or 5.5 V	–	±5	±100	–	±100	µA
I_{OFF}	Power-off leakage current		V_{CC} = 0.0 V; V_I or V_O ≤ 4.5 V	–	±5.0	±100	–	±100	µA
I_{PU}/I_{PD}	Power-up/down 3-State output current[3]		V_{CC} = 2.1 V; V_O = 0.5 V; V_I = GND or V_{CC}; $V_{\overline{OE}}$ = Don't care	–	±5.0	±50	–	±50	µA
I_{IH} + I_{OZH}	3-State output High current		V_{CC} = 5.5 V; V_O = 2.7 V; V_I = V_{IL} or V_{IH}	–	5.0	50	–	50	µA
I_{IL} + I_{OZL}	3-State output Low current		V_{CC} = 5.5 V; V_O = 0.5 V; V_I = V_{IL} or V_{IH}	–	−5.0	−50	–	−50	µA
I_{CEX}	Output high leakage current		V_{CC} = 5.5 V; V_O = 5.5 V; V_I = GND or V_{CC}	–	5.0	50	–	50	µA
I_O	Output current[1]		V_{CC} = 5.5 V; V_O = 2.5 V	−40	−100	−180	−40	−180	mA
I_{CCH}	Quiescent supply current		V_{CC} = 5.5 V; Outputs HIGH, V_I = GND or V_{CC}	–	50	250	–	250	µA
I_{CCL}			V_{CC} = 5.5 V; Outputs LOW, V_I = GND or V_{CC}	–	24	30	–	30	mA
I_{CCZ}			V_{CC} = 5.5 V; Outputs 3-State; V_I = GND or V_{CC}	–	50	250	–	250	µA
ΔI_{CC}	Additional supply current per input pin[2]		Outputs enabled, one input at 3.4 V, other inputs at V_{CC} or GND; V_{CC} = 5.5 V	–	0.5	1.5	–	1.5	mA
			Outputs 3-State, one data input at 3.4 V, other inputs at V_{CC} or GND; V_{CC} = 5.5 V	–	50	250	–	250	µA
			Outputs 3-State, one enable input at 3.4 V, other inputs at V_{CC} or GND; V_{CC} = 5.5 V	–	0.5	1.5	–	1.5	mA

NOTES:
1. Not more than one output should be tested at a time, and the duration of the test should not exceed one second.
2. This is the increase in supply current for each input at 3.4 V.
3. This parameter is valid for any V_{CC} between 0 V and 2.1 V with a transition time of up to 10 msec. From V_{CC} = 2.1 V to V_{CC} = 5 V ± 10%, a transition time of up to 100 µsec is permitted.

AC CHARACTERISTICS

GND = 0 V; t_R = t_F = 2.5 ns; C_L = 50 pF, R_L = 500 Ω

SYMBOL	PARAMETER	WAVEFORM	LIMITS					UNIT
			T_{amb} = +25 °C V_{CC} = +5.0 V			T_{amb} = −40 °C to +85 °C V_{CC} = +5.0 V ±0.5 V		
			Min	Typ	Max	Min	Max	
t_{PLH} t_{PHL}	Propagation delay An to Bn or Bn to An	1	1.0 1.0	2.8 3.9	4.2 5.0	1.0 1.0	4.7 5.4	ns
t_{PZH} t_{PZL}	Output enable time to HIGH and LOW level	2	1.3 3.0	3.5 5.5	4.6 7.0	1.3 3.0	5.5 7.8	ns
t_{PHZ} t_{PLZ}	Output disable time from HIGH and LOW Level	2	1.5 1.0	4.0 3.4	5.4 4.6	1.5 1.0	6.3 5.0	ns

AC WAVEFORMS

V_M = 1.5 V, V_{IN} = GND to 3.0 V

**Waveform 1. Waveforms Showing the Input to Output Propagation Delays**

Waveform 2. Waveforms Showing the 3-State Output Enable and Disable Times

Octal transceiver with direction pin and 30 Ω series termination resistors (3-State)

74ABT2245

TEST CIRCUIT AND WAVEFORMS

Test Circuit for 3-State Outputs

$V_M = 1.5V$

Input Pulse Definition

SWITCH POSITION

TEST	SWITCH
t_{PLZ}	closed
t_{PZL}	closed
All other	open

DEFINITIONS

R_L = Load resistor; see AC CHARACTERISTICS for value.

C_L = Load capacitance includes jig and probe capacitance; see AC CHARACTERISTICS for value.

R_T = Termination resistance should be equal to Z_{OUT} of pulse generators.

| FAMILY	INPUT PULSE REQUIREMENTS				
	Amplitude	Rep. Rate	t_W	t_R	t_F
74ABT	3.0V	1MHz	500ns	2.5ns	2.5ns

SA00012

Octal transceiver with direction pin and
30 Ω series termination resistors (3-State)

74ABT2245

SO20:   plastic small outline package; 20 leads; body width 7.5 mm   **SOT163-1**

pin 1 index

detail X

| 0 | | 5 | | 10 mm |

scale

DIMENSIONS (inch dimensions are derived from the original mm dimensions)

UNIT	A max.	A₁	A₂	A₃	bₚ	c	D(1)	E(1)	e	Hₑ	L	Lₚ	Q	v	w	y	Z(1)	θ
mm	2.65	0.30 0.10	2.45 2.25	0.25	0.49 0.36	0.32 0.23	13.0 12.6	7.6 7.4	1.27	10.65 10.00	1.4	1.1 0.4	1.1 1.0	0.25	0.25	0.1	0.9 0.4	8° 0°
inches	0.10	0.012 0.004	0.096 0.089	0.01	0.019 0.014	0.013 0.009	0.51 0.49	0.30 0.29	0.050	0.419 0.394	0.055	0.043 0.016	0.043 0.039	0.01	0.01	0.004	0.035 0.016	

Note

1. Plastic or metal protrusions of 0.15 mm maximum per side are not included.

OUTLINE VERSION	REFERENCES				EUROPEAN PROJECTION	ISSUE DATE
	IEC	JEDEC	EIAJ			
SOT163-1	075E04	MS-013				~~97-05-22~~ 99-12-27

SSOP20: plastic shrink small outline package; 20 leads; body width 5.3 mm

SOT339-1

detail X

0   2.5   5 mm
scale

DIMENSIONS (mm are the original dimensions)

UNIT	A max.	A_1	A_2	A_3	b_p	c	D[1]	E[1]	e	H_E	L	L_p	Q	v	w	y	Z[1]	θ
mm	2.0	0.21 0.05	1.80 1.65	0.25	0.38 0.25	0.20 0.09	7.4 7.0	5.4 5.2	0.65	7.9 7.6	1.25	1.03 0.63	0.9 0.7	0.2	0.13	0.1	0.9 0.5	8° 0°

Note

1. Plastic or metal protrusions of 0.20 mm maximum per side are not included.

OUTLINE VERSION	REFERENCES				EUROPEAN PROJECTION	ISSUE DATE
	IEC	JEDEC	EIAJ			
SOT339-1		MO-150				95-02-04 99-12-27

Octal transceiver with direction pin and
30 Ω series termination resistors (3-State)

74ABT2245

TSSOP20: plastic thin shrink small outline package; 20 leads; body width 4.4 mm   **SOT360-1**

detail X

0   2.5   5 mm

scale

DIMENSIONS (mm are the original dimensions)

UNIT	A max.	A1	A2	A3	bp	c	D (1)	E (2)	e	HE	L	Lp	Q	v	w	y	Z (1)	θ
mm	1.10	0.15 0.05	0.95 0.80	0.25	0.30 0.19	0.2 0.1	6.6 6.4	4.5 4.3	0.65	6.6 6.2	1.0	0.75 0.50	0.4 0.3	0.2	0.13	0.1	0.5 0.2	8° 0°

Notes

1. Plastic or metal protrusions of 0.15 mm maximum per side are not included.
2. Plastic interlead protrusions of 0.25 mm maximum per side are not included.

OUTLINE VERSION	REFERENCES				EUROPEAN PROJECTION	ISSUE DATE
	IEC	JEDEC	EIAJ			
SOT360-1		MO-153				~~95-02-04~~ 99-12-27

REVISION HISTORY

Rev	Date	Description
_3	20021217	**Product data (9397 750 10846); ECN 853-1761 29292 of 12 December 2002.** **Supersedes data of 16 January 1998 (9397 750 03468).** Modifications: ● Ordering information table: remove "North America" column; remove 74ABT2245N package offering.
_2	19980116	**Product specification (9397 750 03468); ECN 853-1761 18865 of 16 January 1998.** **Supersedes data of 1995 September 06.**
_1	19950906	**Product specification; ECN 853-1761 15701 of 06 September 1995.**

Data sheet status

Level	Data sheet status [1]	Product status [2] [3]	Definitions
I	Objective data	Development	This data sheet contains data from the objective specification for product development. Philips Semiconductors reserves the right to change the specification in any manner without notice.
II	Preliminary data	Qualification	This data sheet contains data from the preliminary specification. Supplementary data will be published at a later date. Philips Semiconductors reserves the right to change the specification without notice, in order to improve the design and supply the best possible product.
III	Product data	Production	This data sheet contains data from the product specification. Philips Semiconductors reserves the right to make changes at any time in order to improve the design, manufacturing and supply. Relevant changes will be communicated via a Customer Product/Process Change Notification (CPCN).

[1]   Please consult the most recently issued data sheet before initiating or completing a design.

[2]   The product status of the device(s) described in this data sheet may have changed since this data sheet was published. The latest information is available on the Internet at URL http://www.semiconductors.philips.com.

[3]   For data sheets describing multiple type numbers, the highest-level product status determines the data sheet status.

Definitions

Short-form specification — The data in a short-form specification is extracted from a full data sheet with the same type number and title. For detailed information see the relevant data sheet or data handbook.

Limiting values definition — Limiting values given are in accordance with the Absolute Maximum Rating System (IEC 60134). Stress above one or more of the limiting values may cause permanent damage to the device. These are stress ratings only and operation of the device at these or at any other conditions above those given in the Characteristics sections of the specification is not implied. Exposure to limiting values for extended periods may affect device reliability.

Application information — Applications that are described herein for any of these products are for illustrative purposes only. Philips Semiconductors make no representation or warranty that such applications will be suitable for the specified use without further testing or modification.

Disclaimers

Life support — These products are not designed for use in life support appliances, devices, or systems where malfunction of these products can reasonably be expected to result in personal injury. Philips Semiconductors customers using or selling these products for use in such applications do so at their own risk and agree to fully indemnify Philips Semiconductors for any damages resulting from such application.

Right to make changes — Philips Semiconductors reserves the right to make changes in the products—including circuits, standard cells, and/or software—described or contained herein in order to improve design and/or performance. When the product is in full production (status 'Production'), relevant changes will be communicated via a Customer Product/Process Change Notification (CPCN). Philips Semiconductors assumes no responsibility or liability for the use of any of these products, conveys no license or title under any patent, copyright, or mask work right to these products, and makes no representations or warranties that these products are free from patent, copyright, or mask work right infringement, unless otherwise specified.

Let's make things better.

**Philips
Semiconductors**

PHILIPS